





Mooloolaba Water Police Station

Kane Constructions was awarded the lump sum contract for the design and construct of a new demountable police station for the Sunshine Coast Water Police.

The QLD Police services were relocating to Mooloolaba spit, to a site which had an unknown future. Therefore they decided on a demountable style building 20x8m. The critical issue, KANE only had 13 weeks to design, build and handover a fully operational police station. The project was worth $1mil and consisted of reception, admin area, toilet/shower facilities, lunch rooms, drug/gun safes and security systems. Also involved the construction of a new boat enclosure and washout area for the police boats.

The site involved the removal of a car park and garden area and installation of a demountable style building 20m from the Mooloolaba beach opposite Mooloolaba spit. The structure and external cladding were built in a factory in Coolum, then transported to site where service rough in/fit off and internal finishes were completed on-site. The building was completed
and operational 13 weeks from date of contract award.

Kane Constructions Pty Ltd
kane.com.au

Client
Queensland Government Department of Community Safety

Consultants
Project Services

Location
Queensland

Value
$1M